



3 Corrected method of condensate removal employing the steam siphon. During retrofit all condensate from pressurized drips and hot water generator was relocated to new condensate pump. The heating system was totally separated from hot water generator and all drips, thereby eliminating any source of hot condensate from affecting the operation of variable vacuum operation.

DRAWING # 3